

N04A

EXHIBITION STAND

N04A


DESCRIPTION

EXHIBITION STAND

Exhibition stand, total size 110x35x220cm.

This structure is made of metal, box profiles 3x3cm, PVC coated, white colour RAL 9003. The stand top is made of MDF d=19mm. JAF Ash veneer or equivalent. Matte transparent water-based varnish is used as the finishing coat.

Brochure and leaflet holders are made of transparent polycarbonate d=5mm, screwed into the MDF.



GENERAL NOTE:

MDF - Medium density fibreboard
MVC - Melamine faced chipboard
HDF - High-density fiberboard

element	name	dimensions axbxc	number
N04A	EXHIBITION STAND	110X38x220	3

 <p>projektovanje, konsalting, inženjering Beograd, Kneza Miloša 82 tel. 011 361 4634, 2656 251 www.domaa.rs e-mail: office@domaa.rs</p>	investor EU DELEGATION AT REPUBLIC OF SERBIA Vladimira Popovića street nr.40, GTC Avenue, block 19a, New Belgrade		
	building & address	EUIC - EUROPEAN UNION INFORMATION CENTER Kralja Milana street nr.7, Belgrade	
 <p>društvo za projektovanje, konsalting i inženjering Dubrovačka 14, Beograd; tel:011/2463-344; e-mail: info@aerprojekt.com</p>	type of design	MAIN DESIGN OF RECONSTRUCTION WITHIN DIMENSIONS AND VOLUME OF EXISTING OFFICE SPACE IN KRALJA MILANA STREET nr. 7 IN BELGRADE	
	drawing	NEWLY DESIGNED - FURNITURE GROUND FLOOR	
part of design ARCHITECTURAL	scale 1:20	date october 2014	drawing No AF_07