LIGHTING TYPE LEGEND

S1	CEILING SURFACE MOUNTED LED LUMINARY/ NARROW BEAM /, 230VAC,4000K,1200lm, IP20			CEILING RECESSED FIXED LED LUMINAIRE, 230VAC,3000K,450lm, IP20, Ø200mm	
S1A	OUTDOOR CEILING SURFACE MOUNTED LED LUMINAIRE/ NARROW BEAM /, , 230VAC,4000K,1200lm			DIMMABLE LED STRIPE 24V,4000K, WITH POWER SUPPLY	
S2	CEILING LED LUMINARY ADJUSTABLE, TRACK MOUNTED, 230VAC,4000K,1330lm, IP20			CEILING SURFACE, BOXED LINEAR LED LUMINAIRE, 230VAC,4000K,3250lm, IP40	
S3	CEILING PENDANT LED LUMINARY 230VAC,4000K,1100lm, IP20			CEILING RECESSED EMERGENCY LED LUMINAIRE (EXIT/RUNNING MAN SIGN), 230VAC, NiCd 1.5Ah,IP20	
S4	CEILING SURFACE, BOXED LINEAR LED LUMINAIRE, 230VAC,4000K,3250lm, IP40			OUTDOOR WALL MOUNTED LED LUMINAIRE, 230VAC,3000K,400lm, IP44	
S4A	CEILING RECESSED, BOXED LINEAR LED LUMINAIRE, 230VAC,4000K,3250lm, IP20	U		WALL MOUNTED LED LUMINAIRE, 230VAC,4000K,1250lm, IP54	
S5	CEILING RECESSED FIXED LED DIMMABLE LUMINAIRE, 230VAC,4000K,2000lm, IP20, Ø200mm				



NETO POVRŠINA PODRUMA

	PROSTORIJA	P(m2)	O(m')	POD	ZID	PLAFON
PO 10	HOL	20.40	30.88	granitna keramika	gips karton	gips karton
PO 11	KANCELARIJA	36.40	25.56	parket	gips karton	gips karton
PO 12	SALA ZA SASTANKE	14.65	15.07	parket	gips karton	gips karton
PO 13	TOALET ZENSKI	4.05	8.27	granitna keramika	granitna keramika	vlagootp. gips kart. pl.
PO 14	TOALET MUSKI	3.92	8.12	granitna keramika	granitna keramika	vlagootp. gips kart. pl.
PO 15	CAJNA KUHINJA	4.92	9.14	granitna keramika	granitna keramika	vlagootp. gips kart. pl.
PO 16	HODNIK	6.84	14.41	granitna keramika	gips karton	gips karton
PO 17	SERVER	3.72	9.75	antistatik pod	gips karton	glet/bojeno
PO 18	TEHNIKA	3.30	8.13	parket	gips karton	glet/bojeno
	UKUPNO	98.20				
PO 19	PODBINSKI PROSTOR	4.15	12.41	cementna kosuljica	glet/bojeno	konstrukcija

DOMAA
projektovanje, konsalting,inženjering
Beograd, Kneza Miloša 82
tel 011 361 4634, 2656 251
www.domaa.rs
e-mail office@domaa.rs

AERPROJEKT
consulting engineers
društvo za projektovanje, konsalting i inženjering
Dubrovačka 14, Beograd; tel:011/2463-344;
e-mail: info@aerprojekt.com

investor	EU DELEGATION AT REPUBLIC OF SERBIA Vladimira Popovića street nr.40, GTC Avenue, block 19a, New Belgrade		
building & address	EUIC - EUROPEAN UNION INFORMATION CENTER Kralja Milana street nr.7, Belgrade		
type of design	MAIN DESIGN OF RECONSTRUCTION WITHIN DIMENSIONS AND VOLUME OF EXHISTING OFFICE SPACE IN KRALJA MILANA STREET nr. 7 IN BELGRADE		
drawing	BASEMENT LEVEL PLAN OF LIGHTING INSTALLATIONS		
part of design ELECTRO	scale 1:75	date october 2014	drawing No E01