


DESCRIPTION

INTERPRETERS' DESK

Interpreters' desk, dimensions 113x60x75cm, P shape. Lateral sides and desktop are made of double white smooth refined chipboard d=2x18mm, with abs tape 2x40mm of the same colour and pattern. The back side is made of single white smooth refined chipboard d=18mm, with abs tape 2x22mm of the same colour and pattern. A ?60mm opening is foreseen at the desktop for cables together with matte aluminum downlight.


TOP PANNEL  
(MDF) double - d=36mm  
white smooth  
with ABS stripe  
d=2x40mm

SIDES  
(MDF) double d=36mm  
white smooth  
with ABS stripe 2x40mm




FRONT VIEW

TOP PANNEL  
(MDF) double - d=36mm  
white smooth  
with ABS stripe  
d=2x40mm



SECTION



TOP VIEW

GENERAL NOTE:

MDF - Medium density fibreboard  
MVC - Melamine faced chipboard  
HDF - High-density fiberboard

element	name	dimensions axbxh	number
N12	INTERPRETERS' DESK	113x60x75	2

 <p>projektovanje, konsalting, inženjering Beograd, Kneza Miloša 82 tel. 011 361 4634, 2656 251 www.domaa.rs e-mail: office@domaa.rs</p>	investor EU DELEGATION AT REPUBLIC OF SERBIA Vladimira Popovića street nr.40, GTC Avenue, block 19a, New Belgrade		
	building & address	EUIC - EUROPEAN UNION INFORMATION CENTER Kralja Milana street nr.7, Belgrade	
 <p>društvo za projektovanje, konsalting i inženjering Dubrovačka 14, Beograd; tel:011/2463-344; e-mail: info@aerprojekt.com</p>	type of design	MAIN DESIGN OF RECONSTRUCTION WITHIN DIMENSIONS AND VOLUME OF EXISTING OFFICE SPACE IN KRALJA MILANA STREET nr. 7 IN BELGRADE	
	drawing	NEWLY DESIGNED - FURNITURE GROUND FLOOR	
part of design ARCHITECTURAL	scale 1:20	date october 2014	drawing No AF_08