


DESCRIPTION

TOILET CABINET

Toilet cabinet, dimensions 104x43x85cm, with a built-in washbasin.  
Washbasin panel is made of Kerrock, which is placed over the substructure made of steel scantlings 3x5cm.  
Sink is also cast in Kerrock.  
The bottom part of the cabinet and inner shelves are made of white smooth refined chipboard d=18mm, with abs tape of the same colour and pattern 2x18mm.  
The door of the bottom part is made of MDF d=19mm, white colour RAL 9003, high gloss.  
Doors do not have handles, but push mechanism enabling opening the door and slow-motion hinges, type Hafele or equivalent - rounded edges of the cabinet on the top section.  
This element is wall mounted, using wall brackets.



GENERAL NOTE:

MDF - Medium density fibreboard  
MVC - Melamine faced chipboard  
HDF - High-density fiberboard

element	name	dimensions axbxc	number
N10	TOILET CABINET	104X43x85	2

 projektovanje, konsalting, inženjering Beograd, Kneza Miloša 82 tel. 011 361 4634, 2656 251 www.domaa.rs e-mail: office@domaa.rs	investor EU DELEGATION AT REPUBLIC OF SERBIA Vladimira Popovića street nr.40, GTC Avenue, block 19a, New Belgrade		
	building & address	EUIC - EUROPEAN UNION INFORMATION CENTER Kralja Milana street nr.7, Belgrade	
 društvo za projektovanje, konsalting i inženjering Dubrovačka 14, Beograd; tel:011/2463-344; e-mail: info@aerprojekt.com	type of design	MAIN DESIGN OF RECONSTRUCTION WITHIN DIMENSIONS AND VOLUME OF EXISTING OFFICE SPACE IN KRALJA MILANA STREET nr. 7 IN BELGRADE	
	drawing	NEWLY DESIGNED STATUS - FURNITURE BSM. LEVEL	
part of design ARCHITECTURAL	scale 1:20	date october 2014	drawing No AF_15