













LIGHTING TYPE LEGEND

S1		CEILING SURFACE MOUNTED LED	5	S6		CEILING RECESSED FIXED LED LIGHT	-
S2		CEILING RAIL LED LIGHT/ SPOT AIMABLE	10	S7		LED STRIP/RIBBON LIGHT - LINEAR	145m1
S3		CEILING SUSPENDED LED LAMP	5	S8		CEILING SURFACE MOUNTED LED LAMP	1
S4		CEILING MOUNTED, BOXED SUSPENSION LINEAR LED	8	S9		WALL SURFACE MOUNTED LINEAR LED LAMP	-
S4A		CEILING RECESSED LINEAR LED LAMP	-	SS		WALL SURFACE MOUNTED OUTDOOR LINEAR LED LAMP	3
S5		CEILING RECESSED LED LAMP	38				



BASEMENT LEVEL NET AREA

	ROOM	A(m2)	P(m')	FLOOR	WALL	CEILING
PR 01	INFO DESK	23.36	21.44	granite tile	gypsum board/painted	gypsum/construction
PR 02	ENTRANCE HALL	20.52	20.32	granite tile	gypsum board/painted	gypsum/wooden
PR 03	MEETING ROOM / SM. CONF.	17.08	19.03	parquete	gypsum board/painted	gypsum/wooden
PR 04	LIBRARY / READING ROOM	19.27	19.20	parquete	gymps./photo wallpaper	gypsum/wooden
PR 05	MULTIFUNCTIONAL HALL	61.89	35.79	wooden tiling	gypsum board/painted	gypsum/wooden
PR 06	TRANSLATORS - CABINS	4.40	8.51	parquete	gypsum board/painted	gypsum board
PR 07	GALLERY	13.05	24.41	parquete	gypsum board/painted	gypsum board
PR 08	MAIN STAIRS	6.02	-	glass floor	gypsum board/painted	wooden railings
PR 09	STAIRS - TRANSLATORS	2.06	-	hardwood	gypsum board/painted	gypsum board
	SUM	167.65				

BASEMENT + GROUND LEVEL

107.0+167.65	274.65
--------------	--------

CEILING TYPE LEGEND

	HANGING CEILING GRID CONSISTED OF VENEERED (MDF) OPEN HOVERING, DIM.60x100mm ON THE AXIAL DISTANCE OF 160mm P=38.49m²		MONOLITHIC GYPSUM CEILING - GYPSUM PANEL /1X1.25/ ON THE GALVANIZED SUBSTRUCTURE 30mm P= 161.63m²		BACKLIGHTED 2 PART CEILING: MADE FROM POLYCARBONATE 5mm HANGED ON THE STEEL SUBSTRUCTURE. TOTAL HEIGHT 150mm. SIDE EDGES ARE MADE FROM ALU PROFILES h=150mm POWDER COATED IN ANTHRACITE GRAY COLOR. P=16.43+12.49=28.95m²
--	-----------------------------------------------------------------------------------------------------------------------	--	---------------------------------------------------------------------------------------------------	--	---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------

<p>projekovanje, konsalting, inženjering Beograd, Kneza Miloša 82 tel 011 361 4634, 2656 251 www.domaa.rs e-mail office@domaa.rs</p>	investor	EU DELEGATION AT REPUBLIC OF SERBIA Vladimira Popovića street nr.40, GTC Avenue, block 19a, New Belgrade		
	building & address	EUIC - EUROPEAN UNION INFORMATION CENTER Kralja Milana street nr.7, Belgrade		
	type of design	MAIN DESIGN OF RECONSTRUCTION WITHIN DIMENSIONS AND VOLUME OF EXISTING OFFICE SPACE IN KRALJA MILANA STREET nr. 7 IN BELGRADE		
	drawing	NEWLY DESIGNED STATUS - CEILING - GROUND FLOOR		
<p>drustvo za projektovanje, konsalting i inženjering Dubrovačka 14, Beograd; tel:011/2463-344; e-mail: info@aerprojekt.com</p>	part of design	scale	date	drawing No
	ARCHITECTURAL	1:75	october 2014	AP 02